

## **ADDENDUM NO. 1**

### **Town of Waynesville – Parks and Recreation Fencing Improvements RFP**

**Date:** 2/16/2025

This addendum is issued to provide clarification and additional scope information. All proposers shall acknowledge receipt of this addendum in their proposal. All other terms and conditions of the original RFP remain unchanged unless modified herein.

Due to the clarifications provided below, the proposal due date is extended to **2/25/2026 at 2:00pm**.

## **1. GENERAL FENCING CLARIFICATION**

For all ballfield sites, the Town is requesting pricing for the following chain link fencing options:

- 9-gauge commercial chain link fabric, black vinyl coated
- 9-gauge commercial core wire with black vinyl coating (equivalent to 6-gauge finished thickness)

For all ballfield fencing, proposers shall include alternate pricing for:

- Bottom tension wire
- Bottom tension rail

## **2. VANCE STREET BALLFIELD**

The Town provides the following clarification regarding fencing at the Vance Street ballfield:

- Fencing shall begin at the termination point of the new backstop CMU wall.
- Fencing shall extend continuously from the wall to fully cover both dugout areas.
- Contractor shall install one (1) 4-foot pedestrian access gate within this section.
- Fencing shall then continue at a height of 6 feet around the outfield perimeter.
- A second 4-foot pedestrian access gate shall be installed along the outfield fence line.
- A 12-foot wide maintenance gate shall be installed along the right field foul line.
- The outfield fence shall be approximately 300 feet from home plate.
- Total fencing length for this site is estimated at approximately 300 linear feet.

Safety netting requirements for this site shall remain as identified in the original RFP.

Contractors shall include all safety netting materials, installation, and integration as part of their base bid.

## **3. RECREATION PARK BALLFIELD**

The Town provides the following clarification regarding fencing at the Recreation Park ballfield:

- Perimeter fencing shall be 4 feet high around the ballfield, excluding the backstop area.
- The backstop fence shall be 16 feet high.
- The backstop shall extend 20 feet in width directly behind home plate.
- Backstop fencing shall also extend 20 feet in length along both the first and third base lines.
- One (1) 12-foot wide maintenance gate shall be included within the perimeter fencing.
- Two (2) 4-foot pedestrian/maintenance access gates shall also be included within the perimeter fencing.
- The outfield fence distance is approximately 200 feet.
- Total fencing length is estimated at approximately 314 to 320 linear feet.

#### **4. DUGOUTS**

Construction, installation, or furnishing of dugout structures is **not included** in this RFP for either the Vance Street Ballfield or the Recreation Park Ballfield. This project includes fencing and safety netting only.

#### **5. DOG PARK**

There are no changes to the scope of work for the dog park. Contractors shall refer to the original RFP for all dog park fencing requirements.

#### **6. GENERAL NOTES**

All fencing and safety netting shall be installed in accordance with industry best practices and applicable local, state, and federal standards. Contractors are responsible for verifying field conditions prior to bidding. The Town reserves the right to adjust quantities as necessary.

**END OF ADDENDUM NO. 1**