

ADDENDUM NO. 2

Town of Waynesville – Parks and Recreation Fencing Improvements RFP

Date: 2/16/2026

This addendum is issued to provide additional clarification to the original RFP and Addendum No. 1. All proposers shall acknowledge receipt of this addendum in their proposal. All other terms and conditions remain unchanged unless modified herein.

1. LINEAR FOOTAGE

Contractors shall disregard all previously stated total linear footage quantities in the original RFP and Addendum No. 1. Linear footage provided in prior documents was for reference only and may not be accurate.

Contractors are responsible for verifying all measurements, field conditions, and quantities necessary to complete the scope of work. The Town strongly encourages site visits prior to bid submission.

2. RECREATION PARK BALLFIELD – FENCE HEIGHT TRANSITION

The Town provides the following clarification regarding fence heights at the Recreation Park ballfield:

- Backstop fencing shall remain 16 feet in height directly behind home plate.
 - Fencing shall transition from 16 feet in height to 10 feet in height along the first and third base line areas to cover the future dugout locations.
 - Beyond the dugout areas, fencing shall transition to 4 feet in height around the remaining field perimeter.
-

3. DUGOUT CONSTRUCTION

Construction, installation, or furnishing of dugout structures is not included in this RFP. This applies to both the Vance Street Ballfield and the Recreation Park Ballfield. The scope of work is limited to furnishing and installing fencing and safety netting only.

END OF ADDENDUM NO. 2